

Modernizing the equipment and automation at FRIPA

The Bavarian tissue producer Papierfabrik Albert Friedrich (FRIPA) recently selected ANDRITZ to expand its stock preparation plant and integrate control of the new equipment into an existing control system. The scope requires modernization of the existing operating stations and servers.



ANDRITZ Automation will compile flow sheets of the existing plant sections, update the instrument lists for previous rebuilds, produce supplemental screen displays,

and compile logic diagrams after finalizing the functions with the mill. Services such as software testing, start-up assistance and delivery of the field instrumentation

are also included in the scope of supply.

The special challenge is to plan a new operating logic and control routine for the modernized stock preparation plant even though some of the documentation has been lost over the years. Existing equipment from a stock prep line that was shut down will be moved to the PM5 line and a screening plant will be modified to now handle the processing of broke. The logic and screen displays on PM5 will be de-

signed to be consistent with the displays implemented in the ANDRITZ PrimeLineCOMPACT machine (PM6) installed in 2008. This uniformity will make it easier for an operator to start and stop the machines in just a few steps. After completion of the programming work in April 2019, start-up is to follow in May. •

ANDRITZ Automation technology installed in Asia's largest effluent treatment plant



A strong move towards digitalization

On the equipment side, ANDRITZ will supply a complete drying and incineration system for expansion of the Bailonggang wastewater treatment plant in Shanghai, China. Construction started at the end of 2018, with first firing expected by the end of 2019 for one of the world's largest effluent treatment plants and the largest in Asia.

ANDRITZ Automation in China will supply the detailed engineering, electrical and automation systems engineering, and installation services (installation supervision and commissioning) as well as the DCS system, MCC control cabinet, and cabling for this massive project. •